



To, **THE ADMINISTRATOR,
Municipal Committee Khanewal.**

No. CE(South)PLGB/TS(408)/2023
Dated: 27th September, 2023

Subject: **TECHNICAL SANCTION.**

Reference your letter No. MC/I&S/KWL/PCP/.105 dated: 26.08.2023 on the subject noted above.

Sr. No	Name of Scheme	Estimated Amount (M)	Technically Sanctioned Amount (M)
1	Comprehensive Sewerage System in Khanewal City (PCP)	1248.44 M	1144.83 M

Estimate provided by your office is technically scrutinized / evaluated and has been found structurally feasible. Returned for further necessary action subject to following conditions complied by procuring agency.

Conditions:-

1. The competent authority of the executing agency and the Engineer in charge shall ensure valid charge, provision of requisite funds, Administrative Approval as per scope and item work provided in the estimate, transfer of requisite land in the name of department, no complaint / inquiry already being conducted by any Department regarding execution of the Project and grant of NOC from Railway department.
2. The competent authority of the executing agency and the engineer in charge shall ensure that the work is carried out after observation of all financial, codal formalities and strictly in accordance with the sanctioned estimate / specifications of tender accepting authority. The responsibility of the authority approving the rates, as the rates provided for estimation purpose only. The tender accepting authority shall also check and satisfy himself regarding quality, durability, economy and lowest market rate in the actual before accepting the rates of supply item. The payment shall be made as per quantity of each item of work/actual work executed at site after record entries with specification and nomenclature as the quantity of each items of works in the estimate is for estimation purpose only and shall not confer any authority for its payment.
3. Rehabilitation of existing sewage treatment plant, as the existing ponds are lined with brick works, it should be rehabilitated and restored in original conditions and no Geo Membran is needed, as the water level is about 60'ft below the ground level and the bottom of anaerobic pond is about 47' ft above and of facultative pond is above 53.6' ft above the ground water table.

4. The quantity of each item of work taken for estimation purpose only. The exact quantity of earthwork will be worked out after conduction leveling before executing of E/W In order to avoid possiblilty of any wrong payment besides preparation of lead chart of E/W showing borrowing areas specifying exact khasra and khatoni number.
The responsibility for feasibility, sustainability, correctness and authenticity of all designs, drawings, plans, technology used, calculation, quality and quantity, successful implementation, avoiding any Irregularities, lies on the Engineer Incharge concern Municipal Committee Khanewal.
5. Before commencing work in the approved project or during the course of work, laboratory report design, which is necessary for any work, the approved estimate must be submitted for Technical Approval.
6. The non-schedule rates as contained in the estimate are for estimate purpose only and should not be taken as authority for payment. The payment of such item will also made after getting competitive rates after observation of all financial and codal formalities.
7. The credit for existing or old dismantled materials should be afforded to the project in accordance with the codal rules and financial procedure properly.
8. The Engineering in charge will certify before making payment be there is no over lapping of the work / item of quality and durability of all terms of works before making the payment.
9. Inform about the schedule of execution.
10. The Non-Schedule rates for items pertaining to the said estimates are approved specifically for this estimate as forwarded by concerned authorities.


27/9/23
(KHALID HUSSAIN)
CHIEF ENGINEER (SOUTH),
PUNJAB LOCAL GOVT. BOARD
HEADQUARTER (MULTAN)

27/9/23